

Kyle Vester

To: rowpermitting@clearwavefiber.com
Subject: RE: ROW/Easement Permit Application -

Approved
Permit: 2026-07-10-04
Expires: October 10, 2026

Kyle Vester, PE
Village Engineer
(708) 444-5500 | kvester@tinleypark.org



ROW/Easement Permit Application

Utility Company or Individual?:	Utility Company
Utility Company Name:	Delta Communications, LLC dba Clearwave Fiber
Email	rowpermitting@clearwavefiber.com
Address	Street Address: PO Box 1229 City: Pooler State / Province: GA Postal / Zip Code: 31322
Name	Courtney Hyde
Title/Position:	Permit Manager
Email	courtney.hyde@clearwavefiber.com
24 Hour Phone Number	(833) 522-6252
Subcontractor Company Name:	Sync Communications
Name	Juan Gonzalez II
Email	gabriel.gonzalez@syncfiber.com
Subcontractor Phone Number	(773) 887-4494

Address	Street Address: 7238 Roosevelt Rd City: Forest Park State / Province: IL Postal / Zip Code: 60130
	Telecommunications
	Underground
	New Construction
Description of work to include means and methods to be used:	Installation of fiber optic cable in 1.25" HDPE conduit by horizontal directional drilling methods to provide broadband services. Installation includes excavation, hand hole splice boxes, backfilling with CA6 compacted granular backfill material and pavement or right-of-way restoration.
Upload the plans/exhibits for review:	P-038453 ILTNL004 City Design.pdf
Have you done utility work with the Village in the last 12 months?	Yes
Upload copies of certifications/permits:	ILTNL004_P-038453_PERMIT_06192026.pdf
Is this an Address or Address Range?:	Address Range
	Address Start: 6471 Oak Forest Ave Address Finish: 6401 175th St
Is this a ROW or Easement?:	ROW
Is there an Utility work order or reference #?	No
Proposed Start Date:	08-25-2026
*Proposed Completion Date:	09-25-2026
Signature	

Title:	Permit Manager
--------	----------------

Date	07-06-2026
------	------------

You can [edit this submission](#) and [view all your submissions](#) easily.

The map displays the 17th Ward of Chicago, divided into seven numbered red regions. The regions are defined by a grid of streets. The streets shown include 173rd St, 174th St, 175th St, 176th St, and 177th St running east-west, and 65th Ave, 66th Ave, and 67th Ave running north-south. Other streets include South St, Oak Forest Ave, Vogt St, 64th Ct, 65th Ct, and 66th Ct. Landmarks and businesses marked on the map include Best Deal Inc, American Legion Post 615, St. George Catholic Church, St. George Catholic Church, Selby H. Hirsch Park, and various parking areas. The map also shows some green spaces and a large body of water on the right side.



- ☐ Approved
- ☒ Approved as Noted
- ☐ Revise and Resubmit
- ☐ For Your Information and Use
- ☐ Incomplete Submittal
- ☐ Not Approved

This submittal has been reviewed only for the limited purpose of checking for general conformance with the design concept and placement of utilities in relation to the Village's underground infrastructure as expressed in the submitted plan documents. Nothing in this review is intended to authorize any aspect of work that is not in accordance with Federal, State, or Local code requirements or other utilities that share the easements.

By: Kyle Vester Date: 7/10/26
Permit: 2026-07-10-04 Expires: 10/10/26

1. Final placement of the FDH cabinet shall be field approved prior to construction beginning.
2. Sod may be required as directed by the Village.
3. No open cutting of Village roads permitted. Potholing is allowed per agreed upon methods.
4. Contractor shall discuss with residents any needed access to private property.

1. THE PREFERRED METHOD OF INSTALLATION WILL BE DIRECTIONAL BORING UNLESS NOTED OTHERWISE.
2. ALL PROPOSED WORK TO BE WITHIN RIGHT OF WAY LIMITS.
3. AN APPROVED PERMIT OR PERMITS AS REQUIRED BEFORE STARTING CONSTRUCTION AND POSTED AT THE JOB SITE.
4. ALL WORK TO COMPLY WITH THE - "GENERAL PROVISIONS" OF THE PERMIT.
5. THE PROPOSED ROUTES WILL BE MARKED WITH PAINT AND/OR FLAGS PRIOR TO CONSTRUCTION.
6. LOCATION OF ALL UTILITIES MUST BE FIELD VERIFIED.
7. CONTRACTOR RESPONSIBLE TO VISUALLY LOCATE CONFLICTING FACILITIES BY DIGGING AND EXPOSING (POTHOLE). IN CONCRETE OR ASPHALT WILL REQUIRE CORE DRILLING.
8. TWO FEET MINIMUM SEPARATION TO BE PROVIDED AT TIMES WHEN WATER, SEWER AND CABLE
9. ALL ASPHALT AND CONCRETE WILL BE REMOVED BY JACK HAMMER AND CUTTING SAW.

AS A GENERAL RULE: RED IS PROPOSED BLUE IS EXISTING

6 FIBER CABLE	6F	6F
12 FIBER CABLE	12F	12F
24 FIBER CABLE	24F	24F
48 FIBER CABLE	48F	48F
96 FIBER CABLE	96F	96F
144 FIBER CABLE	144F	144F
288 FIBER CABLE	288F	288F
432 FIBER CABLE	432F	432F
HDPE CONDUIT - 1 - 1.25"	1C	1C
HDPE CONDUIT - 2 - 1.25"	2C	2C
HDPE CONDUIT - 3 - 1.25"	3C	3C
HDPE CONDUIT - 1 - 2"	2inC	2inC
PROPOSED VAULT	 1A-1A 30X48X36	 1A-1A 30X48X36
PROPOSED FLOWER POT	 1A-1B.D1 10" Round	 1A-1B.D1 10" Round
SPLICE ENCLOSURE - SIZE	 SPL- C	 SPL- C
OFDC 12 PORT ENCLOSURE	 OFDC-C12	 OFDC-C12
PLACEMENT STEPS	3- 1.25" HDPE BORE - 110'	432 F CABLE PLACE - 524'
PROPOSED 288 FDH CABINET	 FEED PANEL - 48 - 48F TAIL DISTRIBUTION PANEL - 288 - DUAL 144F TAILS	
PREVIOUSLY PLACED CONDUIT		

PROPERTY LINE & RIGHT OF WAY _____

EDGE OF PAVEMENT _____ EOP _____

WATER MAIN		W		W		W
GRAVITY SEWER MAIN		S		S		S
STORM SEWER MAIN		ST		ST		ST
SANITARY FORCE MAIN		FM		FM		FM
GAS MAIN		GAS		GAS		GAS
SEWER MANHOLE		EXISTING VAULT		HYDRANT		
POLE ANCHOR		MANHOLE		TREES		
SIGN POST		CATCH BASIN				
EXISTING POLE		BORE PIT		WATER VALVE		

UTILITY AND PROPERTY LINES ARE SHOWN FOR REFERENCE ONLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VALIDATE THE INFORMATION TO ENSURE NO UNDERGROUND UTILITIES ARE DAMAGED AND INSTALLED INFRASTRUCTURE IS WITHIN PUBLIC RIGHT-OF-WAY. TWO FEET MINIMUM SEPARATION TO BE PROVIDED AT TIMES WHEN WATER, SEWER AND CABLE



SIGNED, 18 JUN 2026
EXPIRES, 30 NOV 2027

clearwave fiber™
OSP ENGINEERING

PROJECT:
TINLEY PARK - FDA004
ILTLNL004 - 66TH AVE
TINLEY PARK, ILLINOIS

SHEET #

CV-01

PROJECT SITE:
P-038453